

POLK COUNTY 2024 PROPOSED ROAD CONSTRUCTION

OVERLAYS

- CSAH 14 - 3.9 miles
 - Bituminous Overlay from CSAH 45 to TH 75
 - 11,200 ton Bituminous SP mixture
 - 4,500 ton Cl. 1 mod Aggregate Shouldering (with RAP)
- CSAH 45 - 5.7 miles
 - Bituminous Overlay from TH 220 to TH 75
 - 12,300 ton Bituminous SP mixture
 - 3,100 ton Cl. 1 Aggregate Shouldering
- CSAH 8 - 0.7 miles
 - Bituminous Overlay in McIntosh
 - 1,200 ton Bituminous SP mixture
- CSAH 105 - 0.2 miles
 - Bituminous Overlay in Erskine
 - 500 ton Bituminous SP mixture

GRADING/GRADE WIDENING

- CSAH 12 - 7.7 miles
 - Widening from TH 32 to CSAH 41
 - 130,000 Cu Yd Common Excavation
 - 17,000 ton Bituminous SP mixture
 - 6,500 ton Cl. 1 Aggregate Shouldering
 - 2,700 LF RCP Culverts
- CR 202 - 2.0 miles
 - Grading from CSAH 35 to 2 miles north.
 - 35,000 Cu Yd Common Excavation
 - 800 LF RCP Culverts
- CR 203 - 2.0 miles
 - Grading from CSAH 30 to 2 miles north.
 - 35,000 Cu Yd Common Excavation
 - 400 LF RCP Culverts
- Roundabout
CSAH 21 - 1.0 miles
TH 75 - Roundabout at CSAH 21 and TH 75
 - Aggregate Base/Concrete Paving/Bituminous Mixture

BASE ONE/AGGREGATE BASE

- CSAH 35 - 12.5 miles
- CSAH 63 - Aggregate Base/Base One
- 30,000 ton Cl. 1 Mod Aggregate Base

BRIDGE CONSTRUCTION

- Columbia Township - Concrete Beam Span Bridge

POLK COUNTY MINNESOTA

PROPOSED CONSTRUCTION - 2024

